

ADDENDUM NO. 1

DATE: June 18, 2020

BID DATE: **Friday, June 26, 2020, 5:00 PM local prevailing time**

TO: Railworks Track Services, Inc., ARolf@railworks.com
Fritz-Rumer-Cooke, ccooke@fixrail.com
Associated Railroad Contractors, Inc., micah@associatedrailroad.com

RE: LOUISVILLE & JEFFERSON CO. RIVERPORT RAILROAD TIE REPLACEMENT

FROM: Qk4
1046 East Chestnut Street
Louisville, Kentucky 40204
(502) 719-7926
abartley@qk4.com

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated June 2020. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

This Addendum consists of **3 pages**.

Bid date is unchanged.

ALL PLANS AND SPECIFICATIONS REMAIN UNCHANGED EXCEPT AREAS NOTED BELOW IN BID FORM.

1. Tie installation primarily located in northern half of LJCRP property.
2. Tamping of new ties required daily during installation.
3. Regulating/Dressing of shoulders required daily during tie installation.
4. 21,120 TF of production surfacing will encompass tie installation areas as well as other select areas within 7 miles.
5. 1,900 crossties have been selected to be replaced by new 7"x9"x8'6" crossties. Installation will also include new prime grade 5/8"x6" track spikes per CSX spiking pattern specifications. *2,055' of guard rail will need to be removed and reinstalled after installation of roughly 374 crossties and surfacing is complete. See exhibit on page 3 of this addendum for project area.
6. 500 tons of clean local #4 limestone ballast shall be installed and areas to be tamped and regulated.

This page to replace Section 5.00 in original specifications:

SECTION 5.00 BID PROPOSAL

NAME OF BIDDER: _____

BUSINESS ADDRESS: _____

TO: Louisville & Jefferson County Riverport Authority
6900 Riverport Drive
Louisville, Kentucky 40258

Ladies and Gentlemen:

We have examined the local conditions affecting the proposed work, all the Contract Documents issued by the office of Qk4, Inc., 1046 E. Chestnut St., Louisville, Kentucky, 40204, including the Instruction to Bidders, this Proposal form, the General Conditions, Agreement, Performance Bond and the Specifications, Plans, Drawings and all Addenda and Exhibits for the project, and also the site of the work, and hereby propose and agree:

5.01 LUMP SUM BID PRICE

To furnish all labor, new materials, tools, equipment, utility and transportation services, insurance, bonds and everything necessary to perform and complete, in a workmanlike manner, the replacement of railroad ties per requirements of the Contract Documents, at the Lump Sum Bid Price stated in the following schedule:

TIE REPLACEMENT: WOOD TIES
(UP TO 1,900 TOTAL TIES)

\$ _____ EACH = _____ TOTAL

FURNISH/INSTALL #4 LIMESTONE BALLAST
(500 NET TONS)

\$ _____ /NET TON = _____ TOTAL

SURFACING (PRODUCTION TEAM)
(21,120 TRACK FEE)

\$ _____ /TF = _____ TOTAL

PROJECT TOTAL = _____

Guard Rail Exhibit

